

SZ-170-S

Warranty

- ♦ 5 years Manufacturer Warranty
- ♦ Warranty on Electrical Performance: 8years power output

Manufacturing

- ♦ Original cell sorting system ensures the best electric cell match
- ♦ EL-Testing before packing.
- ♦ Comprehensive module power testing.

Performance

- ♦ Higherer module efficiency and compact size. Weakened hot-spot effect, lower module failure
- ♦ rate and increased stability by shingle-tech.
- ♦ Special connection method lowers the internal resistance and ensures better performance than traditional connection with busbar.
- ♦ IP67 rated junction box, reliable cables and standard MC4 connectors improve the stability



Mechanical Data

Standard Test Conditions AM=1.5, E=1000W/m2, TC=25°C

Nominal Power	170W
Cell Type	Monocrystalline
Cell Efficiency	22%
Maximum Power Current (Impp)	7.14A
Maximum Power Voltage (Vmpp)	23.82V
Open-circuit Voltage (Voc)	28.31V
Short-circuit Current (Isc)	7.57A
Maximum System Voltage	500V
Output Tolerance	±3%
Cable	700mm / 2.5mm2
Connector Type	MC4 / MC4 Compatible
Module Structure	Aluminum Frame / Glass / EVA / Backsheet
Junction box rating	IP67
Diode	
Working Temperature	-40~+80°C

Packaging

Module Dimensions	1230*670*30mm
Module Weight	8.4kg
Package	Single Package
Pieces per Pallet	30pcs
Gross Weight per Pallet	308kg
Pallet Dimensions	1260*1100*850mm

SOLMAX NEW ENERGY B.V.

Address: Defensiedok 18,3433 KL, Nieuwegein, The Netherlands

Tel: +31-307855708

info25@solarfam.nl

